

A clearing fuel market for AeroMAPS

Step 1: formulation, integration, verification and policy results

Branch `feat/fuel-clearing-step1`

September 22, 2026

Abstract

AeroMAPS is currently *told* the share of each fuel and computes the resulting cost. This work inverts that: a convex optimisation programme is given a policy — an obligation, a penalty, growth limits, capacities — and returns both the volume of each fuel produced and the price at which it clears. The programme is solved once over all regions, all pathways and all prospective years, so it anticipates: it builds ahead of an obligation it can see coming.

This report states the model in full, describes every parameter, and separates two classes of result that are easy to confuse: those obtained from the optimisation kernel *alone*, at a demand fixed from outside, and those obtained with the kernel *chained into AeroMAPS*, where the price it sets feeds airline costs, airfares and therefore back into demand. It reports what was verified, what was found to be broken along the way, and what the mode cannot yet do.

The headline results: with scarcity switched off the new mode reproduces the existing one to 1.9×10^{-9} across the whole chain; with scarcity on it produces a quantity AeroMAPS has never had — a scarcity rent — and that quantity turns out to be exactly what makes the coupled fixed point hard to reach.

Contents

1	What this is, and what it answers	2
2	The model	2
2.1	The programme	2
2.2	Every parameter	3
2.3	The prices the model produces	3
2.4	What the airline actually pays	3
2.5	Two choices that keep the problem convex	4
3	How it plugs into AeroMAPS	5
3.1	Two levels of result, and why the distinction matters	5
3.2	What the discipline replaces	6
3.3	Decide on net, report on gross	6
4	Verification	6
5	Results without the chain (kernel only)	7
5.1	It reproduces the current allocator	7
5.2	Perfect foresight builds ahead of the obligation	7
5.3	Which parameters move the answer	7
5.4	Capacity sized on the obligation is undersized	7

6	Results with the chain (coupled)	7
6.1	End-to-end reproduction	7
6.2	Scarcity reaches the traffic loop	8
6.3	The coupled saturation grid	8
6.4	The coupled fixed point fails at $w = 1$	8
7	Policy cases	9
7.1	Eligibility differing by region	9
7.2	A sub-target within the target	9
7.3	A carbon tax, and nothing else	10
7.4	The same destination by two instruments	11
8	Defects found, and one general lesson	11
9	Limitations	12
10	Where this goes next	12

1 What this is, and what it answers

The existing AeroMAPS energy chain answers: *given these fuel shares, what does the scenario cost?* It cannot answer *given this policy, what fuel gets made?*, because the quantity produced in response to a policy is exactly what a market determines and the current model is handed it as an input.

The fuel market adds a second mode, opt-in and default off. Both modes coexist; they answer different questions. The new one takes an obligation, a penalty for missing it, a production cost and a set of physical limits per pathway, and returns:

- **volumes** — how much of each fuel is produced, in each region, each year;
- **prices** — what the energy is worth at the margin, what the obligation costs to comply with, and what a growth limit is worth relaxing.

The prices are not assumed or calibrated. They are the Lagrange multipliers of the programme’s constraints, which is what makes convexity worth paying for: a convex programme has one optimum, and its multipliers are certified prices that do not depend on where the solver started.

2 The model

2.1 The programme

Over regions $r \in \{1..R\}$, pathways $p \in \{1..P\}$ and prospective years $t \in \{1..T\}$, with decision variables $q_{r,p,t} \geq 0$ (energy produced, MJ) and $x_{r,t} \geq 0$ (obligation released by paying the penalty, MJ):

$$\min_{q, x} \sum_t \delta_t \left[\underbrace{\sum_{r,p} \left(c_{r,p,t} q_{r,p,t} + \frac{c_{r,p,t} \gamma_{r,p} K_{r,p,t}}{n+1} \left(\frac{q_{r,p,t}}{K_{r,p,t}} \right)^{n+1} \right)}_{\text{production cost, integral of the marginal cost}} + \sum_r B_{r,t} x_{r,t} \right] \quad (1)$$

subject to, for every region r and year t :

$$\sum_p q_{r,p,t} = D_{r,t} \quad \text{energy balance} \quad \rightarrow \lambda_{r,t}^E \quad (2)$$

$$\sum_{p \in \mathcal{S}_r} q_{r,p,t} + x_{r,t} \geq m_{r,t} D_{r,t} \quad \text{obligation} \quad \rightarrow \lambda_{r,t}^M \quad (3)$$

$$\sum_{p \in \mathcal{N}_r} q_{r,p,t} + x_{r,t}^{\text{sub}} \geq \mu_{r,t} D_{r,t} \quad \text{sub-obligation} \quad \rightarrow \lambda_{r,t}^S \quad (4)$$

$$q_{r,p,t} \leq s_{r,p} + (1 + g_{r,p}) q_{r,p,t-1} \quad \text{growth limit} \quad \rightarrow \lambda_{r,p,t}^R \quad (5)$$

with $q_{r,p,0} \equiv q_{r,p}^{\text{init}}$ given. $\mathcal{S}_r$ is the set of pathways *eligible* for region r 's obligation and $\mathcal{N}_r \subseteq \mathcal{S}_r$ the narrower set for its sub-obligation.

Three properties of this programme carry the design.

One solve, not one per year. Constraint (5) ties t to $t - 1$, so solving year by year would discard anticipation. Sustainable output above the obligation in early years is a *result*, not an artefact: with perfect foresight the cheapest way to meet a step is to be ready before it arrives.

Convex, so the multipliers are prices. λ^E is the marginal cost of energy; λ^M is the compliance price. A fixed point found by iteration would not come with that guarantee.

The growth limit is a sum, not a maximum (§2.5).

2.2 Every parameter

2.3 The prices the model produces

The *marginal price* of a pathway aggregates the constraints one unit of it relaxes:

$$\text{MC}_{r,p,t} = \lambda_{r,t}^E + \lambda_{r,t}^M \mathbf{1}[p \in \mathcal{S}_r] + \lambda_{r,t}^S \mathbf{1}[p \in \mathcal{N}_r]. \quad (6)$$

A sub-mandated unit carries both obligation multipliers. That is not double counting: it genuinely relaxes two distinct constraints.

2.4 What the airline actually pays

This section answers a question the earlier write-ups left implicit.

Two prices exist for each pathway and they are not the same. The **average cost** is what the fuel produced actually cost, per unit:

$$\text{AC}_{r,p,t} = c_{r,p,t} \left(1 + \frac{\gamma_{r,p}}{n+1} \left(\frac{q_{r,p,t}}{K_{r,p,t}} \right)^n \right), \quad (7)$$

against the marginal price (6). The gap between them is **inframarginal rent** — profit earned on every unit produced more cheaply than the last one. The pricing weight interpolates:

$$\boxed{\text{mfsp}_{r,p,t}^{\text{mkt}} = (1 - w) \text{AC}_{r,p,t} + w \text{MC}_{r,p,t} - \underbrace{\left(\text{net}_{r,p,t} - \text{gross}_{r,p,t} \right)}_{\text{tax wedge, §3.3}}} \quad (8)$$

and AeroMAPS's existing machinery then weights that across pathways into the one number the airline sees, $\{\text{type}\}_{\text{mean_mfsp}} = \sum_p \text{share}_p \cdot \text{mfsp}_p^{\text{mkt}}$, which drives operating cost, airfare and demand.

So: fuel cost, or compliance, or both?

- At $w = 0$ (the default) the airline pays **the production cost of the fuel it buys, and nothing else**. λ^M is computed and reported but *never reaches the airline*. It is a shadow price — an economic diagnostic saying what the obligation is worth — not a charge.
- At $w = 1$ the airline pays the marginal price, which by (6) **is** energy price *plus* compliance price on eligible pathways. Here compliance is passed through in full.
- Between, it pays a w -weighted blend.
- **It is never “compliance only”**. Compliance is a premium *on top of* the energy price, not a substitute for it.
- The **carbon tax** is added by `DirectOperatingCosts` as its own, separate line — which is precisely why (8) subtracts the tax wedge back out (§3.3).

One thing the airline does *not* pay, and should: the buy-out payment Bx appears in objective (1) but in no price output. If the market releases part of the obligation, that penalty is currently borne by nobody in the cost chain. At $w = 1$ the *rate* is signalled correctly (λ^M is capped at B), but the *payment* is not accounted. This is a known gap, not a modelling choice.

A useful consistency check falls out: with no scarcity at all, $\lambda^E = c_k$ (kerosene) and $\lambda^M = c_s - c_k$, so a sustainable pathway’s marginal price is exactly c_s — which is also its average cost. The two endpoints of (8) coincide and w is inert. w **only matters where something is scarce**, from *either* the capacity term or a binding growth limit.

2.5 Two choices that keep the problem convex

Capacity squeezes, it does not wall. Production is not capped. Instead the marginal cost rises with utilisation, $c(1 + \gamma(q/K)^n)$, whose integral appears in (1). A hard cap would make the price jump discontinuously at $q = K$; since that price feeds airfares, which feed demand, which feeds fuel demand, a jumping price makes the coupled loop oscillate instead of settle. Figure 1 shows the shape and the rent.

The growth limit has to be a sum. AeroMAPS’s optimisation mode limits growth by Eq. (12) of the published work — the *more permissive* of a relative rate and a fixed volume addition:

$$E_t \leq \max\{(1 + \tau)E_{t-1}, E_{t-1} + \Delta E\}. \quad (9)$$

The region under a maximum of two affine functions is not a convex set (Figure 2, right), so (9) cannot be handed to a convex solver. This is not a tolerance problem; the feasible set is the wrong shape. Constraint (5) replaces the maximum with a *sum*, which is its convex outer relaxation: it admits everything (9) admits, plus a margin **measured at 0.73 %, independent of g** .

The seed s in (5) is Eq. (9)’s volume branch ΔE , so it is *not* a free parameter: the published calibration (0.2 EJ/yr at an ASK share of 0.1549) puts it at about **1.5 % of annual demand**. It matters — on the bench the seed moves the compliance price by a factor 4.3 across a plausible range.




Figure 1: Left: n decides *when* the squeeze bites, not how hard. Note the consequence — below $q = K$ a larger n gives a *smaller* markup, which is why stiffness reduces the price on a bench running under capacity. Right: the gap between marginal and average cost is the rent that w interpolates across.




Figure 2: Why the published growth limit cannot go into the programme, and what replaces it. Right: two admissible points whose connecting line is inadmissible — the definition of a non-convex set.

3 How it plugs into AeroMAPS

3.1 Two levels of result, and why the distinction matters

This section answers the second question the earlier write-ups left implicit.

Results in this report come from one of two set-ups, and conflating them would be a serious misreading.

Why the policy cases are kernel-only, deliberately. Chaining scales every price effect by roughly a tenth (§6.3) and changes no *ordering* at $w = 0$, while costing minutes per case — and at $w > 0$ it introduces a convergence problem (§6.4) that would sit between the reader and the policy question. The kernel-level results are therefore the *policy* answer; the coupled results are what tells you how much of it survives the demand response.




Figure 3: Where the market sits. Shaded: the discipline added by this work. The loop on the left is closed only in coupled mode, and only carries a discontinuous quantity when $w > 0$.

3.2 What the discipline replaces

In market mode the existing allocator `EnergyUseChoice` is **not instantiated**: the market decides the volumes rather than being handed shares. It emits the same nine output families under the same names, computed by a *shared* function extracted from the allocator rather than a second copy — two copies would drift, and the failure is silent, since a share family disagreeing with its volumes rescales CO₂ with no error raised.

The mode is one configuration key, default off, propagated to each region as a process-level keyword. It is refused outside the unified-MDA execution mode, and three guards raise at set-up rather than producing plausible-looking numbers: drop-in fuels only, top-down cost model only, exactly one residual pathway.

3.3 Decide on net, report on gross

The market chooses using `net_mfsp` — cost *including* carbon tax and subsidies — because that is what determines which pathway is marginal. This is not cosmetic: on the bench a carbon tax of only 5 EUR/t already narrows the sustainable premium by 3 %, and extrapolating the emission factors the premium reaches zero near **164 EUR/t**, where the ordering reverses and the market buys sustainable fuel unprompted. A market clearing on gross cost could never produce that.

But `DirectOperatingCosts` adds the carbon tax as its own line. Publishing a net-basis price would count the tax twice — hence the wedge subtracted in (8). **Decide on net, report on gross, and the tax is counted once.**

A *passenger*-level tax is deliberately excluded from the objective: it is uniform across fuels, so it cannot change which pathway is marginal. It still reaches the market through demand, which is the correct channel.

4 Verification

An analytic case pins the conventions. One region, one year, saturation known in closed form, so both prices are known exactly. This caught a sign error that documentation could not have: `cvxpy` reports the equality’s multiplier negated, so the energy price came out as -0.012 against an expected $+0.012$ — a plausible number with the wrong sign.

38 kernel tests , covering the balance, the obligation, the growth limit, scale invariance, continuity and input hygiene.

Complementary slackness, across seven regimes. A multiplier may be non-zero only where its constraint is tight. This single property is what all three real defects (§8) violated, and nothing tested it. It is now parametrised over the *edges* — zero obligation, full obligation, a constraint that cannot bind — because a mid-range case sees none of them. Worst residual: 1.4×10^{-8} , solver noise; the phantom compliance price scored 0.46 on the same measure.

5 Results without the chain (kernel only)

5.1 It reproduces the current allocator

Given the reference run’s shares, with saturation off and the growth limit loose, the market lands on the reference allocation with a residual below 10^{-8} of demand — an order of magnitude under solver noise.

5.2 Perfect foresight builds ahead of the obligation

At $g = 15\%/yr$ against the ReFuelEU steps, region A holds **more** sustainable fuel than it owes in every year between steps: 14.1 % in 2034 against a 6 % obligation, 28.9 % in 2039 against 20 %. The growth limit cannot take it from 6 % to 20 % in the year the step lands, so it starts early. Sustainable fuel is the expensive option and discounting penalises early spend, so it overshoots by the *minimum* that clears the next step — which is what a firm reading a published mandate would do.

The penalty is needed exactly once, at the 2035 step and only at the tightest growth limit. The compliance price is **zero in every year where the market is ahead**.

5.3 Which parameters move the answer

Two readings that a single-parameter view gets wrong. γ ’s **1.7 % is misleading**: it was measured at one stiffness, and at $n = 1$ the same range moves the uplift 4 %→16 %. The two saturation parameters are not separable. And γ ’s real effect at this baseline is on the *compliance* price, which it moves +57 % — scarcity raises the cost of the obligation well before it raises the average fuel bill.

The penalty is inert until it is cheap enough to be worth paying. The obligation’s own marginal cost here is 0.0546 EUR/MJ. Set B above that and it never binds; set it below and the market stops building and pays instead, and the *delivered* price falls 8.3 %. A penalty priced under the cost of compliance is a subsidy to non-compliance.

5.4 Capacity sized on the obligation is undersized

With a binding growth limit, anticipation pushes utilisation to $q/K = 2.01$ between steps: the market builds twice the plant the obligation asks for. Saturation disciplines it — at $\gamma = 1$ the peak falls to 1.30.

6 Results with the chain (coupled)

6.1 End-to-end reproduction

With nothing scarce, the coupled mode must reproduce the existing model. It does, and not only in the volumes:

An independent confirmation fell out: the compliance price came back at 0.01083, which is the *net*-basis premium (0.010830) and not the gross one (0.011170). The decide-on-net rule is doing what it claims.

6.2 Scarcity reaches the traffic loop

Expensive fuel makes tickets dearer and some journeys do not happen. AeroMAPS could not previously produce that chain of consequences *from a fuel policy*, because nothing in it priced scarcity.

6.3 The coupled saturation grid

Swept through the full MDA, so volumes respond. Delivered price % / RPK % against the no-scarcity run:




Figure 4: The same grid drawn. Gaps are cells that did not converge; they are not interpolated over.

Two results survive the feedback intact. The kernel-level *ordering* holds — uplift still falls monotonically in n . And **the traffic response is consistently about a tenth of the price response**: +42.1 % on price gives −4.7 % on RPK. That ratio is the product of two independently measured transmissions (fuel is 13.1 % of the airfare; demand elasticity 0.888). Rule of thumb for this bench: **a 10 % fuel-price rise costs about 1.2 % of traffic**.

6.4 The coupled fixed point fails at $w = 1$

At $w = 1$ the loop does not converge under AeroMAPS’s default settings: the residual stalls at 2.1×10^{-1} after 200 iterations. Damping helps but does not close it; acceleration fixes *some* cells (3 of 12), not all.

Instrumenting per iteration locates it exactly. Everything is converged to 10^{-12} except **two years**, where the *compliance price swings 100 % of its own magnitude while the volumes move 1–2 %*.

The mechanism, and it is not “prices are volatile”. The measured loop gain is ≈ 0.32 , far below 1 — a gain that low cannot diverge. It is a *discontinuity*. A 2 % demand wobble flips the obligation between binding and slack; λ^M jumps between a positive value and zero when it does. The primal barely notices; the multiplier is a step function across that boundary. The iterate settles into an exact period-3 limit cycle.

So w decides whether the model couples to a well-defined function of its own state. At $w = 0$ the delivered price is the *average cost* — a function of volumes, which move 1 %; the jump never reaches the traffic loop and the MDA converges in 40 iterations. At $w = 1$ the price contains λ^M , and duals at an active-set boundary are not well-defined functions of the state.

A natural explanation was tested and **rejected**: the bad years sit next to a ReFuelEU step, so the staircase obligation looked responsible. Replacing it with a smooth ramp through the same points still fails. Smoothing moves the boundary rather than removing it — with a binding growth limit there is always some year where it stops binding. This is intrinsic to coupling an MDA fixed point to the duals of a constrained intertemporal programme, not a quirk of the regulation.

Practical consequence: $w = 0$ is solid (12 of 12, default settings). $w > 0$ is a research problem, not a scenario dial, until the boundary behaviour is understood.

7 Policy cases

Five pathways — kerosene, HEFA from waste oil, HEFA from crop oil, alcohol-to-jet, e-fuel. *Kernel-level* (Table 2). Conclusions are about orderings and mechanisms; the numbers are illustrative.

7.1 Eligibility differing by region

One ReFuelEU-like region excludes crop feedstock; the other allows it; same headline obligation.




Figure 5: Same target, different portfolios. The coloured band is mandated fuel; the dashed staircase is the obligation, so colour above the line is anticipation.

Excluding a cheap feedstock is dearer every year except the last: +60 % on the compliance price in 2030, +139 % in 2040, and −10 % in 2050.

The mechanism is the growth limit. Denied the cheap option, region A builds e-fuel early and arrives at 2049 with a 30.9 % base; the permissive region coasts on crop oil and arrives with 5.0 %. When the obligation jumps 42 %→70 %, all four of the permissive region's pathways hit their growth limits at once.

Cheap options early leave you worse placed for a steep step later — a result a share-allocation model cannot produce, because it has no notion of what was built when.

7.2 A sub-target within the target

ReFuelEU's synthetic-fuel trajectory, on top of the headline obligation:

By 2050 e-fuel *exceeds* the 35 % target, because the forced early build-out leaves a bigger base to grow from.




Figure 6: The cost, and the reason for it. Left: the exclusion is dearer in every year until the last; the sawtooth is each obligation step landing and the market catching up. Right: what it bought — a built-out e-fuel industry.




Figure 7: Left: the sub-target tracked exactly, then overshoot. Middle: the headline obligation gets cheaper throughout. Right: the sub-target's own price.

A number that invites the wrong conclusion. The main compliance price falls in every year — by 53 % in 2040. That is *not* the sub-target making compliance cheaper: an extra constraint on the same programme can only make the optimum dearer, and it does. **Total production cost +10.7%; fuel bill +5.1 %.** What falls is the price of *one instrument* because the other is now doing that work. Quoting the compliance price alone would show a policy paying for itself while it does the opposite.

7.3 A carbon tax, and nothing else

Every obligation switched off.

Below about 170 EUR/t a carbon tax on aviation fuel buys nothing at all. The mix stays 100 % kerosene and the intensity does not move from 88.6 gCO₂/MJ — it is pure revenue.

Then a cliff between 400 and 600, where kerosene goes from 67 % to zero and intensity falls 71.2 → 15.7. Not an artefact: kerosene's tax-inclusive cost ($0.0120 + 88.6\tau/10^6$) crosses e-fuel's ($0.0550 + 5.0\tau/10^6$) at $\tau = 514$ EUR/t, and the whole residual switches at once, because nothing distinguishes one litre of kerosene from another. **A tax moves one crossing point at a time, so its effect is a staircase, not a slope.**




Figure 8: Nothing, then everything.

7.4 The same destination by two instruments

The tax is **10.8 % cheaper** and **13 % dirtier**: it buys the cheapest sustainable fuel, the obligation’s feedstock rule buys a cleaner one.

The environmental work is done by the eligibility rule, not by the volume target. A mandate written in volumes is not an emissions instrument. It becomes one only through the rules about what counts.

One confound: the tax case has no obligation, so no eligibility rule applies to it and crop oil is available. That is realistic — eligibility rules only exist inside mandates — but it makes this a *restricted mandate against an unrestricted tax*, not instrument against instrument at equal restriction.

8 Defects found, and one general lesson

Three defects of the *same family* were found, all of them producing plausible-looking numbers rather than errors.

1. **A price for an obligation that does not exist.** Where $m = 0$, constraint (3) is implied by $q, x \geq 0$ — redundant, so its multiplier is free. The solver reported up to 0.0112 EUR/MJ, roughly the whole cost of kerosene, in years with no obligation.
2. **An indeterminate split at a 100 % obligation.** There the obligation forces conventional supply to zero, so (2) and (3) have the same active rows and only their *sum* is determined. The solver split the identical problem three different ways, including a *negative* energy price.
3. **A jump at a binding/slack boundary** — §6.4. The same thing dynamically, and the one that stops the solver.

In every case a constraint stopped being independent and its multiplier became arbitrary. The first two are now pinned to their meaningful KKT values; the third is not fixable that way, because the discontinuity is real.

A convex programme that solves is not a programme that is right. The saturation term was first written as $a q^{n+1}$ with $a = c\gamma/((n+1)K^n)$ — algebraically correct, numerically unusable: a carries K^{-n} and the coefficients spanned 35 orders of magnitude at $n = 16$. Half the parameter grid refused to solve; worse, *where it did solve it returned a suboptimal point*, 0.13 % dearer, which showed up as a **3.4 % error in the delivered price** — at the exact settings the whole sensitivity table was built on. The solver reported **optimal** both times.

Rewriting it in the utilisation it is actually a function of, $[c\gamma K/(n+1)](q/K)^{n+1}$, made all 36 cells solve. The only thing that caught the wrong answer was scoring the returned point against the objective *independently of the solver*.

9 Limitations

- **Regions do not interact.** Every constraint is per region and the objective is a plain sum, so solving jointly and separately agree to solver noise. There is no **leakage**: a stricter region cannot import compliance from a looser one. This is the single most important missing mechanism for policy work.
- **$w > 0$ does not reliably converge** (§6.4).
- **The buy-out payment reaches no one** (§2.4).
- **No learning curve** anywhere in AeroMAPS, so the cost of entry is a constant and every price dynamic comes from the model’s own scarcity terms.
- **Bottom-up costs are excluded “for now”**, and not for the usual reason. A vintage *mix* effect makes average cost *fall* as volume rises, which makes the cost integral concave and the duals stop being prices. A loop is not the obstacle; the sign is.
- **2050 is the horizon** and also the steepest step, so results turning on “what is built by the end” are partly a terminal condition.
- **Emission factors and four of the five costs are assumed.**

10 Where this goes next

1. **Inter-regional trade**, which is what the global (non-namespaced) discipline was built for. At step 1 it is global in plumbing, not economics.
2. **Understand the $w > 0$ boundary behaviour**, or decide the model reports the rent without charging it.
3. **Pass the buy-out payment through** to the cost chain.
4. **Make `cvxpy` a proper optional dependency** before the mode ships.

Symbol	Shape, unit	Meaning and provenance
$D_{r,t}$	(R, T) , MJ	Drop-in energy demand. In coupled mode this is <code>energy_consumption_dropin_fuel</code> , an output of the fleet chain — which is what makes the market part of a loop.
$c_{r,p,t}$	(R, P, T) , EUR/MJ	Production cost per unit energy at zero utilisation. Taken as <code>{p}_net_mfsp</code> : the cost the buyer actually faces, carbon tax and subsidies included (§3.3). Flat in time on the bench — AeroMAPS has no learning curve, so all price dynamics come from the model, not the supply curve.
$m_{r,t}$	(R, T) , fraction	The obligation: minimum eligible share of demand. A <i>fraction</i> , not a percentage — validated, because a silent factor of 100 here would be invisible downstream.
$\mathcal{S}_r$	(R, P) , boolean	Eligibility , not chemistry: which pathways count towards region r 's obligation. The same fuel may count in one jurisdiction and not another.
$\mu_{r,t}, \mathcal{N}_r$	$(R, T), (R, P)$	Sub-obligation and its narrower eligible set — ReFuelEU's synthetic-fuel target. Optional; absent by default.
$B_{r,t}$	(R, T) , EUR/MJ	Penalty ("buy-out") per unit of unmet obligation. Caps λ^M : nobody pays more to comply than to not comply. Without it an unreachable obligation makes the programme <i>infeasible</i> rather than expensive.
$K_{r,p,t}$	(R, P, T) , MJ	Capacity <i>scale</i> , not a cap: the output at which the pathway starts to strain. ∞ disables saturation. Exogenous at step 1.
$\gamma_{r,p}$	(R, P)	Saturation intensity — how much dearer the next unit is at full utilisation. 0 switches the term off entirely.
n	scalar ≥ 0	Saturation stiffness — how <i>abruptly</i> the extra cost arrives. $n \rightarrow \infty$ recovers a hard cap, which is what the soft form exists to avoid.
$g_{r,p}$	(R, P) , /year	Growth limit: relative expansion allowed year on year.
$s_{r,p}$	(R, P) , MJ	Growth <i>seed</i> . Not optional in practice: with $q^{\text{init}} = 0$ and $s = 0$, (5) pins the pathway at zero forever. Not a free dial either — it is Eq. (12)'s volume branch (§2.5).
$q_{r,p}^{\text{init}}$	(R, P) , MJ	Production in the last historical year; the growth limit's initial condition.
δ_t	scalar	Discount factor $(1 + \rho)^{-t}$. Decides how far ahead of a step it is worth building.
w	scalar $\in [0, 1]$	Pricing weight . Decides who keeps the scarcity rent (§2.4). The single most consequential parameter.

Table 1: Inputs. R regions, P pathways, T prospective years.

Symbol	From	Reads as
$\lambda_{r,t}^E$	(2)	What the next unit of energy costs. Set by whichever pathway is on the margin.
$\lambda_{r,t}^M$	(3)	What one more unit of obligation costs. Bounded above by B . Zero in any year where the market is already ahead of the obligation — a slack constraint costs nothing.
$\lambda_{r,t}^S$	(4)	The same, for the narrower target.
$\lambda_{r,p,t}^R$	(5)	What it would be worth to be allowed to grow faster. Zero where the limit is not in the way.

	Kernel only	Chained into AeroMAPS
What runs	The convex programme alone. NumPy arrays in, arrays out. No AeroMAPS import.	The programme as a GEMSEO discipline inside the full multi-regional MDA.
Demand $D_{r,t}$	Fixed from outside — taken from a stored reference run.	An output of the model , responding to the price the market sets.
Loop closed?	No. Price has no effect on demand.	Yes: price $\rightarrow$ operating cost $\rightarrow$ airfare $\rightarrow$ elasticity $\rightarrow$ demand $\rightarrow$ price.
Cost per case	~ 0.03 s	minutes
Used for	Formulation, verification, parameter sweeps, all policy cases .	Reproduction end-to-end, convergence, the coupled grid.

Table 2: The two levels. Everything in §5 and §7 is kernel-only; everything in §6 is coupled.

Parameter	Swept	Spread in delivered price
Pricing weight w	$0 \rightarrow 1$	37.3 %
Stiffness n	$1 \rightarrow 16$	16.3 %
Penalty B	$0.02 \rightarrow 0.30$	8.3 %
Growth limit g	$0.10 \rightarrow 1.20$ /yr	3.8 %
Intensity γ	$0 \rightarrow 4$	1.7 %
Discount rate ρ	$0 \rightarrow 0.08$	0.0 %

2050, both regions	reference	market	worst rel., all years
hefa_fog_energy_consumption	9.84171e12	9.84171e12	1.1e-09
hefa_fog_share_dropin_fuel	70	70	1.9e-09
dropin_fuel_mean_mfsp	0.019819	0.019819	1.8e-10
dropin_fuel_mean_co2_emission_factor	41.1	41.1	1.0e-09
co2_emissions_passenger	493.04	493.04	6.3e-10
airfare_per_rpk	0.0867286	0.0867286	5.1e-11
rpk	1.98233e13	1.98233e13	1.6e-11

Table 3: Worst relative difference across every variable and year: 1.9×10^{-9} .

	no scarcity	scarce, $w = 0$	scarce, $w = 1$
Delivered price 2050	0.019819	0.021839 (+10.2 %)	0.04020 (+103 %)
Max compliance price	0.01083	0.047886	—
RPK 2050	1.98233e13	−1.2 %	−10.8 %
CO ₂ 2050	493.04	−1.2 %	—

	$n = 2$	$n = 4$	$n = 8$	$n = 16$
$w = 0, \gamma = 0.5$	+11.2/−1.3	+5.2/−0.6	+1.8/−0.2	+0.4/−0.0
$w = 0, \gamma = 1$	+21.9/−2.5	+10.2/−1.2	+3.6/−0.4	+0.8/−0.1
$w = 0, \gamma = 2$	+42.1/−4.7	+19.6/−2.3	+7.1/−0.8	+1.6/−0.2
$w = 1, \gamma = 0.5$	<i>did not converge</i>			
$w = 1, \gamma = 1$	<i>n.c.</i>	+102.9/−10.8	<i>n.c.</i>	<i>n.c.</i>
$w = 1, \gamma = 2$	+186.2/−18.0	+133.2/−13.6	<i>n.c.</i>	<i>n.c.</i>

Table 4: 15 of 24 cells converge: all 12 at $w = 0$, only 3 of 12 at $w = 1$.

	2030	2040	2050
e-fuel, no sub-target	0.0 %	5.4 %	41.0 %
e-fuel, with sub-target	1.2 %	15.0 %	46.2 %
Main compliance price	0.01800 → 0.01721	0.08718 → 0.04103	0.09100 → 0.06908

Same 70 % sustainable, 2050	Production cost	Intensity	Mix
Obligation (crop excluded)	0.03427	36.5	41 % e-fuel, no crop
Carbon tax, 515 EUR/t	0.03056	41.3	33 % e-fuel, 18 % crop